SHIMOGA DIVISION.

Notification dated 3rd October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. on Monday the 19th October 1936, for " Reconstructing the damaged culvert at 4/12 of Sagar-Shiralkoppa Road." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited a sum of Rs. 200 as earnest money, and be superscribed " Tender for reconstructing the damaged culvert at 4/12 of Sagar-Shiralkoppa Road," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Enigneer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Works should be according to Departmental specifications.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 1,000 and the work should be completed by the end of February 1937.

16. Cement will be supplied by the Department and the cost with centage recovered.

Abstract estimate for reconstructing the damaged culvert on old foundations with Laterite brick in lime mortar at 4/12 of Sagar-Shiralkoppa Road, in Sagar Taluk.

Serial No.	Items of work	Per	Rate	Quantity	Rates tendered by the contractor	
					In figures	In words
	I. APPROACH ROAD.	..	Rs. a. p.			
1	Clearing site of tank and cleaning the existing damaged culvert after demolishing the superstructure upto basement	L. S.	..	..		
2	Earthwork to road with 1'—0" depth of cushion on top of bridge and wheel guard stones	„	..	..		
3	Collecting, breaking and stacking broken quartz metal with lead ..	C.yd.	3 8 0	46		
4	Collecting and stacking gravel, including lead of one mile	„	0 12 0	15		

Serial No.	Items of work	Per	Rate	Quantity	Rates tendered by the contractor	
					In figures	In words
			Rs. a. p.			
5	Picking the road surface	S.yd.	0 0 2	228		
6	Consolidation of metal by stone road roller, including spreading and watering and tamping	C.yd.	0 6 0	46		
7	Spreading and consolidation of gravel	,,	0 4 0	15		
8	Collecting and spreading sand ..	,,	0 8 0	..		
	II. CULVERT PROPER.					
1	Earthwork excavation	C.yd.	0 4 0	158		
2	Filling in foundation with surki concrete	C.ft.	0 4 6	483		
3	Constructing roughly dressed stone in surki mortar in foundation ..	,,	0 5 6	1,047		
4	Constructing laterite bricks in surki mortar	,,	0 4 6	5,097		
5	Providing and fixing cement concrete slabs	,,	0 10 0	301		
6	Rough stone boulder pitching, including lead	C.yd.	2 0 0	89		
7	Fixing available burnt stone slabs 6″ thick, with dressing wherever required	S.ft.	0 1 6	1,140		
8	Constructing parapet wall of laterite masonry 2′—0″ in height, 1½′ in thickness with plastering, white washing, etc., complete, including extra length beyond the slab portion with good foundations	R.ft.	1 0 0	156		
9	Deep cement pointing 1:3	Sqr.	4 0 0	39·60		
10	Rough stone revetment to slopes of banks including lead	C.yd.	2 0 0	107		
11	Baling out water	L. S.	...	..		
12	Draft and approach clearing ..	C.yd.	...	...		

Notification dated 3rd October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M., on Monday the 19th October 1936 for "Construction of Staff quarters required in connection with the Electrification of Shimoga Town at Shimoga." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited a sum of Rs. 1,500 as earnest money, and be superscribed "Tender for Construction of Staff quarters required in connection with the Electrification of Shimoga Town at Shimoga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Work should be according to departmental specifications.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 5,000 and the work should be completed by the end of April 1937.

16. Cement will be supplied by the department and the cost with centage recovered.

17. Mysore timber alone should be purchased by the contractor from the Mysore Government Forest timber yards.

Abstract estimate for construction of Quarters required in connection with the Electrification of Shimoga Town.

Serial No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
	One independent block with a latrine :— Quarters for Line Inspector or Senior Operator, as per Drawing No. G. 379 with a latrine as per Drawing No. G. 257.					
1	Earthwork excavation for foundation and filling in basement with tamping	C.yd.	0 3 6	71		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 5 0	649		
3	Size stone in lime mortar, including bond slabs 6′ apart	,,	0 6 6	1,141		
4	Burnt brick in lime mortar ..	,,	0 4 6	2,323		
5	Burnt stone slabs 6″ thick, roughly dressed and fixed in lime mortar ..	S. ft.	0 12 0	158		
6	Burnt stone slabs 6″ thick, single line dressed and fixed in lime mortar ..	,,	0 12 6	206		
7	Burnt stone slabs 6″ thick, two line dressed and fixed in mortar ..	,,	0 13 0	69		
7 (*a*)	Drilling holes in cill slabs for fixing door frames	Each	0 8 0	14		
8	Providing R.S. beams, including painting anticorrosive paint, two coats and fixing in position, etc., complete	Cwt.	12 0 0	4½		
9	Teakwood doors with 3″×5″ frames and 1¼″ thick without bottom sill, panelled shutters with iron hinges, etc., complete	S.ft.	1 4 0	144		
10	Teakwood doors with 3″×5″ frames and 1¼″ thick, half shutters at bottom panelled and top half with expanded metal fittings with hinges, etc.; complete	,,	1 8 0	23		

Serial No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
11	Teakwood windows with 3″×4″ frames and battened shutters 1″ thick with iron hinges, etc., complete with C. I. fan lights at top ..	S.ft.	1 8 0	151		
12	Reinforced brick concrete terrace with one course of bevelled brick on edge with reinforcements both longitudinal and crosswise with cement concrete 2″ between joints and over bricks with 2″ to 4″ thick brick kuppi on top and two courses flat tiles including chunam plastering both top and bottom faces ..	Sqr.	70 0 0	2·66		
13	Teakwood work wrought and put up including two coats of wood oiling, etc., complete	C.ft.	4 8 0	64·30		
14	Roofing with I Class Mangalore tiles on teak reepers 2″×1″ including tying edge tiles,etc., complete ..	Sqr.	28 0 0	11·27		
15	Providing with I Class Mangalore ridge tiles set in cement mortar ..	R.ft.	0 12 0	62		
16	Teakwood plain eave board 9″ alround, including two coats of wood oiling.	„	0 8 0	130		
17	Providing expanded metal fittings to verandah with 3″×4″ teakwood frame and grey graphite painting, two coats, etc., complete ..	S.ft.	0 14 0	83		
17(*a*)	Providing and fixing cement perforated ventilators with two coats of cement wash	S.ft.	1 4 0	9		
18	Providing and fixing teakwood Work Almirahs with shutters and two cross planks, including two coats of wood oiling	„	1 4 0	48		
19	Boxing girder with brick in cement mortar and binding with wire and chunam plastering	R.ft.	0 12 0	24		
20	Constructing parapet wall with burnt brick in lime mortar 1½′ high, 9″ thick, including lime plastering and whitewashing, two coats, complete.	„	1 0 0	48		
21	Grey Graphite painting, two coats ..	Sqr.	4 8 0	10·78		
22	Cement pointing (1: 3) to basement ..	„	4 0 0	2·41		
23	Grey colour washing, two coats basement	„	0 5 0	2·41		
24	Lime plastering, ½″ thick	„	3 14 0	45·36		
25	Plain cornice alround terrace ..	R.ft.	0 4 0	49		
26	Flooring with 1½″ cement concrete 1 : 3 : 6 over lime concrete and ½″ cement plastering 1: 3 and cut into tile pattern.	Sqr.	25 0 0	8·14		
27	White washing, two coats	„	0 4 6	45·36		
28	Providing chimneys for bath and kitchen with sinks	Each				
29	C.I. rain water pipes	„				
30	Cement concrete drain	R.ft.				
31	Levelling ground and forming ..	C.yd.				
32	Constructing a latrine as per details given separately	..	..	..		

Serial No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
	Two blocks with two latrines :—Quarters for Operators as per Drawing No. G. 383 with latrine as per Drawing No. G. 257.					
1	Earthwork excavation for foundation and filling in basement with tamping	C.yd.	0 3 6	90		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 5 0	822		
3	Size stone in lime mortar, including bond slabs 6′ apart	S.ft.	0 6 6	1,690		
4	Burnt brick in lime mortar ..	C.ft.	0 4 6	2,516		
5	Burnt stone slabs 6″ thick, single line dressed and fixed in lime mortar, complete	S.ft.	0 12 6	669		
6	Burnt stone slabs 6″ thick, two line dressed and fixed in lime mortar, complete	„	0 13 0	16		
7	Providing R.S. beams including painting anticorrosive paint, two coats and fixing in position, etc., complete ..	Cwt.	12 0 0	6·64		
8	Teakwood doors with 3″×5″ frames and battened shutters of 1¼″ thick including locking arrangements, etc., complete	S.ft.	1 4 0	318½		
9	Teakwood windows with frames of 3″×4″ and battened shutters 1″ thick with iron bars, hooks, hinges, etc., complete	„	1 8 0	30		
9(*a*)	Do with C.I. fanlights at top	„	1 8 0	83		
10	Teakwood ventilators with battened shutters and iron bars, etc., complete	„	1 14 0	36		
10(*a*)	Providing cement perforated ventilator as per design furnished with two coats of cement wash ..	„	1 4 0	9		
11	Teakwood doors with 3″×5″ frames and shutters panelled to bottom half and expanded metal to top, including ventilators at top ..	„	1 10 0	54½		
12	Providing expanded metal fittings to verandah with 3″×4″, teakwood frame and grey graphite painting, two coats, etc., complete ..	„	0 14 0	101		
13	Reinforced brick concrete terrace with one course of brick on edge and 2″ joints alround with longitudinal and crosswise reinforcements in cement concrete (1 : 2 : 4) for joints alround bricks and at top of it for 2″ to 3″ and 2″ to 6″ brick kuppi and two layers of flat tiles over it, including lime mortar plastering both at top and bottom surface and neat finishing, etc., complete	„	70 0 0	3·36		
14	Teakwood work wrought and put up including, two coats of wood oiling	C.ft.	4 8 0	60·96		

Serial No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
15	Roofing with I Class Mangalore tiles on teak reepers 2″×1″ including tying edge tiles with wire ..	Sqr.	28 0 0	11·84		
16	Providing and fixing I Class Mangalore ridge tiles set in cement mortar	R.ft.	0 12 0	76		
17	Constructing brick in lime mortar parapet wall 9″ thick and 1′ high, including lime plastering and white washing, two coats, etc., complete ..	„	1 0 0	60		
18	Plain cornice for terrace	„	0 4 0	62¾		
19	Teakwood plain eaveboard 9″ with two coats of wood oiling ..	„	0 8 0	134		
20	Providing and fixing teakwood almirahs with shutters and 3″×4″ frames, hinges, etc., with wood oiling, etc., complete	S.ft.	1 4 0	96		
21	Grey graphite painting, two coats ..	Sqr.	4 8 0	15·09		
22	Cement pointing to basement 1 : 3 ..	„	4 0 0	2·13		
23	Lime mortar plastering, ½″ thick ..	„	3 14 0	52·53		
24	White washing, two coats	„	0 4 6	52·53		
25	Boxing R.S. beams with brick in cement mortar 1: 5, including cement reinforcements, etc., complete ..	R.ft.	0 12 0	22		
26	Constructing sinks in bath room with cement plastering, ½″ thick 1 : 6 ..	S.ft.	1 0 0	18		
27	Mortar bands over roof, burnt brick in mortar including chunam plastering, two coats	R.ft.	0 4 0	40		
28	Grey colour washing to basements ..	Sqr.	0 5 0	2·13		
29	Flooring with 1½″ cement concrete 1 : 3 : 6 over 4″ jelly concrete in lime mortar and ½″ cement plastering and cut into tile pattern ..	„	25 0 0	8·34		
30	Providing and fixing rain water pipes	Each	..	..		
31	Cement concrete drain	R.ft.	..	..		
32	Levelling ground and clearing site ..	C.yd.	..	..		
33	Construction of two latrines as per details given separately ..	..	..	..		
	Two Blocks with two latrines :—Quarters for coolies as per Drawing No. G. 381 with latrines as per Drawing No. G. 257.					
1	Earthwork excavation for foundation and filling in basement, including tamping	C.yd.	3 6 0	64		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 5 0	581		
3	Size stone in chunam mortar ..	„	0 6 6	1,132		
4	Burnt brick in chunam mortar ..	„	0 4 6	2,128		
5	Burnt stone slabs, single line dressed and fixed in chunam mortar, etc., complete	S.ft.	0 12 6	294		
5(*a*)	Burnt stone slabs, two line dressed and fixed in chunam mortar and cement pointed	„	0 13 0	69		

No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
6	Teakwood work wrought and put up, etc., complete with two coats of wood oiling	C.ft.	4 8 0	61.30		
7	Roofing with 1st class Mangalore tiles on teakwood reepers 2″×1″, including tying edge tiles and wood oiling to reepers	Sqr.	28 0 0	13.68		
8	Chunam plastering ½″ thick ..	„	3 14 0	47.64		
9	Teakwood doors with 3″×5″ frames with battened shutters 1¼″ and iron hinges, etc., complete	S.ft.	1 4 0	78		
10	Teakwood windows with 3″×4″ frames with battened shutters 1″ thick with iron bars, including iron hinges, etc., complete	S.ft.	1 8 0	60		
11	White washing, two coats	„	0 4 6	47.64		
12	Cement pointing to basement ..	Sqr.	4 0 0	1.37		
13	Colour washing do	„	0 5 0	1.37		
(a)	Cement perforated ventilators with two coats of cement wash	„	1 4 0	9		
14	Providing and fixing 1st class Mangalore ridge tiles and cement pointed	R.ft.	0 12 0	80		
15	Painting, two coats with grey graphite painting	Sqr.	4 8 0	6.46		
16	Teakwood plain eaveboard 9″ in height	R.ft.	0 8 0	148		
17	Flooring with 4″ stone jelly concrete in lime mortar over which 1½″ cement concrete 1 : 3 : 6 and plastered with cement mortar ½″ thick and cut into tile pattern ..	Sqr.	25 0 0	7.80		
18	Providing and fixing teakwood almirahs with 3″×4″ frames, including hinges, etc., complete with wood oiling, etc.	S.ft.	1 4 0	48		
19	Constructing sinks, providing shelves, smoke pipe and glass tiles	Each	..	..		
20	Mortar bands over roof, burnt brick in lime mortar, including plastering and white washing, etc., complete	R.ft.	0 4 0	24		
21	Cement concrete drain as per design ..	„	..	..		
22	Levelling ground and clearing site ..	C.yd.	..	..		
23	Construction of two latrines as per details separately noted ..	..	..	..		
	Construction of latrines (five in number) as per Drawing No. G. 257 (one for Line Inspector or Senior Operator, two for Operators and two for Cooly blocks.)	..	..	..		
1	Earthwork excavation for foundations and filling in basement with tamping	C.yd.	0 3 6	4		
2	Sizestone in cement mortar 1 : 5 ..	C.ft.	0 7 0	130		
3	Burnt brick in cement mortar 1 : 6 ..	„	0 5 6	201		
4	Cement mortar plastering ½″ thick 1 : 3	Sqr.	6 0 0	5.12		
5	Cement pointing to basement 1 : 3 ..	„	4 0 0	0·46		

No.	Items of work	Per	Rate of the estimate (not sanctioned)	Quantity	Rate tendered by the contractor	
					In figures	In words
	c		Rs. a. p.			
6	Flooring with $1\frac{1}{2}''$ cement concrete 1 : 3 : 6 over 4″ lime concrete and $\frac{1}{2}''$ cement plastering 1 : 3, complete and cut into tile pattern ..	Sqr.	25 0 0	03·8		
7	Flooring with burnt stone slabs 6″ thick, two line dressed over 3″ stone jelly lime concrete and cement pointing the joints, complete	S.ft.	1 4 0	7		
8	Providing Soalge pits	Each	..			

N. SUBBA RAO,
Executive Engineer.

MEDICAL DEPARTMENT

VICTORIA, MINTO OPHTHALMIC, VANI VILAS AND CHILDREN'S HOSPITALS, BANGALORE.

Abstract Notification.

Sealed tenders, in triplicate, on half-sheet sized foolscap paper will be received at the Office of the Secretary, Victoria, Minto Ophthalmic, Vani Vilas and Children's Hospitals, Bangalore (in the Victoria Hospital) by the undersigned at 11 A.M. on Monday the 9th November 1936 for the supply of " diet and other articles " required for the use of the said Hospitals, from 1st January 1937 to 31st December 1937 (both days inclusive). For further particulars, please refer to the detailed notification published in pages 1930-1932, Part VI of the *Mysore Gazette,* dated 24th September 1936.

Abstract Notification.

Sealed tenders, in triplicate, on half-sheet sized foolscap paper will be received at the Office of the Secretary (Victoria Hospital), Victoria, Minto Opthalmic, Vani Vilas and Children's Hospitals, Bangalore, by the undersigned at 11 A.M. on Monday the 9th November 1936, for the supply of Cows' Milk required for the use of the said Hospitals from 1st January 1937 to 31st December 1937 (both days inclusive). For further particulars, please refer to the detailed notification published in pages 1529-1530, Part VI of the *Mysore Gazette,* dated 24th September 1936.

Abstract Notification dated the 18th September 1936.

Sealed tenders, in triplicate, on half-sheet foolscap paper will be received at the Office of the Secretary, Victoria, Vani Vilas and Minto Hospitals, Bangalore (in his Office in the Victoria Hospital) by the undersigned at 11 A.M. on 31st October 1936 (Saturday) for the supply of Bedding and Clothing required for the use of the Children's Hospital, Bangalore. For details, please refer to part VI, page 1535 of the *Mysore Gazette,* dated 24th September 1936.

H. N. PALLEGAR,
Secretary.